SCOPE OF WORK

Unity Tower, Kesavadasapuram

Area under consideration - 20,000 sq. ft.

BUILDING MAINTENANCE & COMPLIANCE

1. Waterproofing

- Transportation and setting up of scaffolding to work in these areas.
- Identify and repair all water leakage points within the building.
- Apply appropriate waterproofing treatments to terraces, exterior walls, joints, and other affected surfaces.
- Replace rusted, damaged, or broken pipelines contributing to leakage.
- Ensure all treated areas are sealed and protected from future seepage.

2. Cleaning

- Clean all areas affected by leakage or maintenance work.
- Remove stains, dust, debris, and moisture patches.
- Restore cleaned areas to a neat and usable condition.

3. Painting – Common Areas

- Prepare walls and surfaces by cleaning, scraping, and filling cracks.
- Apply primer and two coats of high-quality paint(2 coats) to lobbies, staircases, corridors, and other shared areas.
- Ensure neat finishing and uniform color across all common zones.
- Interior - Asian Paints
- Exterior - Asian Paints Ultima
- Damp Proofing - 2K, Dr. Fixit

Total Rate - Rs.65 per sq. ft. X 20,000 = Rs. 13,00,000

4. Civil Work

- Carry out minor structural repairs including plastering, crack filling, and surface patching.
- Replace or repair damaged slopes, kerbs, or masonry components.
- Reinforce weak or deteriorated areas identified during inspection.
- Execute any additional civil repairs needed for building safety and upkeep.

Amount - Rs.1,50,000

---

5. Manhole & Drainage Cleaning

- Open and clean all manholes within the property.
- Removal of interlock to access the blocked pipes if necessary
- Remove sludge, debris, and blockages to ensure proper flow.
- Clear blocked drainage pipelines using high-pressure jetting or manual rodding as required.
- Check for any pipe damage and report necessary repair work.
- Ensure all manholes are securely closed after cleaning.
- Properly refixing the interlock with a metal layer underneath.

Amount - Rs.1,75,000

---

6. Generator Removal

- Inspect the unused generator and evaluate scrapping/resale options.
- Coordinate with vendors for safe dismantling and disposal.

Amount - As per vendor rate

---

7. Fire Safety Compliance

- Conduct a full assessment of the building’s fire safety status.

- Identify gaps and required corrective actions to meet fire safety norms.
- Install or upgrade fire extinguishers, emergency lighting, safety signs, and directional markers.
- Ensure fire-stair access is secured and compliant.
- Prepare the building for fire safety inspection and certification if needed.

Amount - Vendor quote to be sent separately

---

8. Lift/Elevator Replacement

- Replacement of the lift based on the submitted vendor quotation.
- Coordinate dismantling, installation, electrical integration, testing, and commissioning.
- Ensure all work complies with statutory lift safety standards and that certification is obtained after installation.

Amount - Rs. 9,05,600

---

9. Sheet Roof Replacement (Generator Area)

- Remove the old or damaged sheet-roof section located near the generator.
- Inspect the supporting framework for corrosion or weakness and repair if needed.
- Install new weather-resistant Tata roofing sheets with proper alignment and sealing.
- Ensure the new roof is durable, rust-protected, and provides adequate rain protection.
- Dispose of the old sheet material responsibly.

Amount - Rs. 175 per sq. ft. X 50 = Rs. 8,750

---

10. Regular Cleaning & Monthly Maintenance Service

- Clean common areas **twice a month**, including entrances, corridors, staircases, and open spaces.
- Perform monthly inspections covering plumbing, electrical, structural, and safety-related aspects.
- Report observations, issues, and recommendations to the building group regularly.
- Provide a monthly service charge for the ongoing maintenance package.

Amount - To be finalised/negotiated later

MATERIALS & WORKMANSHIP

- All materials used will be of standard ISI-certified quality.
- Work will be carried out as per industry best practices and safety standards.
- Any additional work not mentioned in the scope will be quoted separately.

EXCLUSIONS

- Major structural alterations
- Electrical/Plumbing beyond the mentioned scope
- Approvals or permits
- Waste disposal charges (if not included)

PAYMENT TERMS

- 20% advance upon work order
- Remaining payment as stages during the course of the project when necessary
- Payment preferred via Bank Transfer/UPI
- Quote validity: **30 days**

WORK DURATION

Estimated time for completion: **8-10 Weeks**
Work scheduling will be coordinated to avoid disruption to commercial operations.

Yours Sincerely,

Mr. Varghese Joseph
9847258208