Ref:AX/NI/2861/25
19-11-2025

To,

Mr. Varghese Joseph
Unity Tower
Kesavadasapuram
TVM.

Sub: Supply, Installation, Testing & Commissioning of 1 No. 05 Passenger Lift in your esteemed Building at TVM.

Dear Sir,

We acknowledge with thanks the receipt of the subject enquiry. We are pleased to submit our Quotation/Agreement against supply, installation, testing & commissioning of the passenger elevator as per the technical specifications, terms & conditions enclosed herewith.

Axima gives top priority to meet each customer's desire and is trying the best to ensure every product and its services with perfect quality. After all insisting to give you the best quality whether the installations or services is the only thing we can do for you. Axima elevator licensed manufacturing company **(KL/LEEM/033/2019),** always insists on guarantee the best qualities of safety related fixtures. Our main objective is enhancing efficiency at all levels as such production, marketing, services etc.

Thanking you and assuring you of our best services at all times and looking forward to a long and fruitful business association.

Yours faithfully,
For Axima Elevators (P) Ltd.

Azhar U.R

Sales Engineer.
7902216216

Ref:AX/NI/2861/25
19-11-2025

Specification

MODEL	AXM MR model
CAPACITY	05 person, 340 Kg,
SPEED(mps)	1 mps
TOTAL TRAVEL HIGHT	
FLOOR DESIGNATION	B,G,1,2,3
STOPS	05 Stops (all opening on the same side)
CONTROLLER TYPE	AXM3MR
DRIVE	VF Regenerative (Closed Loop)
POWER SUPPLY	400/415 Volts (3 Phase AC)
OPERATION	Full collective operation
MACHINE	Geared (Located in shaft on top of guide rails)
CAR FINISH	Stainless Steel Finish 304 (Fireproof)
FALSE CEILING TYPE	SS Design Ceiling
VENTILLATION	Cross flow fan
HAND RAILS	Stainless Steel Finish Handrails on rear car panels.
FLOORING	PVC Tiles
CAR DOOR FINISH	Stainless Steel Finish 304 (Fireproof)
LANDING DOORS FINISH	Stainless Steel Finish 304 (Fireproof)
CAR & LANDING DOOR SILLS	Extruded Aluminium

79 02 213 213
79 02 215 215
90 72 868 660
AXIMA ELEVATORS (P) LTD.
CTM Complex, Room No: 32 Ambadi Lane, Veliyannur, Thrissur-680021
aximaelevators@gmail.com

Ref:AX/NI/2861/25
19-11-2025

PIT DEPTH	1500 mm
OVERHEAD	5400 mm
HOISTWAY DIMENSIONS	1550 mm W * 1400 mm D
CAR DIMENSION	900 mm W * 950 mm D
CAR& LANDING ENTRANCE	Auto Centre Opening about 700 mm wide x 2000 mm height.
DOOR OPENING	700 mm Centre Opening
DOOR OPERATOR	DC Door Operator Automatic VVVF
HALL FIXTURES FACE PLATE	SS Hair line face plates for Car and Landing boards with Micro Stroke button
STANDERD FEATURES	Automatic Rescue Device(ARD) Overload Device Emergency Fireman's Service Emergency Car Light Unit Infrared Curtain Door Protection Door Time Protection Emergency Alarm Button Manual Rescue Operation Auto Fan Cut Off

79 02 213 213
79 02 215 215
90 72 868 660
AXIMA ELEVATORS (P) LTD.
CTM Complex, Room No: 32 Ambadi Lane, Veliyannur, Thrissur-680021
aximaelevators@gmail.com

Ref:AX/NI/2861/25
19-11-2025

PRICE QUOTE AND TERMS OF PAYMENT DETAILS

MS Powder Coated Finished Doors & cabin 05 P with Geared machine (MR)

Contract Value as per Technical Specification	**: Rs. 7,07,700/-**
GST @ 18%	**: Rs. 1,27,386/-**
Total Amount	**: Rs. 8,35,086/-**

(INR Eight Lakh Thirty Five Thousand and Eighty Six Only)

SS Finish Doors & cabin 05 P with Geared machine (MR)

Contract Value as per Technical Specification	**: Rs. 7,67,000/-**
GST @ 18%	**: Rs. 1,38,060/-**
Total Amount	**: Rs. 9,05,060/-**

(INR Nine Lakhs Eighty Thousand One Hundred and Eight Only)

Terms Of payment

a) 40 % of total amount against agreement as advance.
b) 30% of total amount against the delivery of first part materials (Guide Rail and fixing accessories , Landing doors and fixing accessories) at the site.
c) 20% of total amount against the delivery of second part materials (Motor and fixing accessories , Cabin and fixing accessories) at the site
d) 10% of total amount against completion of the elevator but before the handing over the elevator for use.

Note: Our offer is valid for your acceptance for a period of 30 days from the date of this offer.

The above offer is inclusive of:

a) Freight and Unloading
b) Erection, Testing and commissioning
c) Minor building works and scaffolding in lift shaft
d) 12 months free warranty from the date of Handing over the lift
e) AMC charges will be 3% of Lift Value (Total amount) for Normal AMC and 6% of Lift Value (Total amount) for Comprehensive AMC.

79 02 213 213
79 02 215 215
90 72 868 660
AXIMA ELEVATORS (P) LTD.
CTM Complex, Room No: 32 Ambadi Lane, Veliyannur, Thrissur-680021
aximaelevators@gmail.com

Ref:AX/NI/2861/25
19-11-2025

DETAILS OF ITEMS/WORK ESSENTIAL FOR THE EXECUTION OF THE CONTRACT BUT NOT FORMING PART OF THE SCOPE OF OUR OFFER

1. All preparatory building work such as elevator shaft with enclosure, water proof elevator pit with drain, machine room with necessary R.C.C. Slab, Sockless, M.S. Channel for elevator machinery, etc.

2. Machine room flooring including any reinforcement etc., necessary for load bearing, machine bed casting, trapdoor, windows, doors provision of suitable ventilation arrangement to maintain machine room temperature under 40^0 C.

3. Hoisting Beam or hook in the machine room for lifting purpose above the trap door having a minimum capacity of 1.00 ton but as per actual requirement of capacity of the elevator.

4. Any necessary tanking lining or reinforcements in the elevator pit, sockless in the elevator pit for buffers.

5. Lift entrance should be cleared as per our requirement

6. Do the arrangements for buffer spring casting.

7. Light point in the elevator shaft opposite each landing, machine room and in the pit.

8. Proper guarding and closed fencing of the elevator shaft and all other openings.

9. 230V Single phase and 415V three phase 50 Hz A.C. Power supply with suitable switch fuse units of required capacity in the machine room for Erection/Installation. Timely provision of permanent power supply for testing purposes. Effective double earthing in the machine room. Lightning arrestor and other electrical protective devices necessary to meet statutory requirement.

10. Electric wiring between the clients main meter board and the clients main switch board in the machine room.

11. **Copy of the building drawing, plan & elevation approved by local authority should be provided.**

12. **Copy of the main electric schematic drawing approved by Electrical Inspectorate should be provided. In case of any delay in receipt of documents from the customer side the balance payment should be made within two weeks after completion of the lift.**

13. **Lift Running License: - We will get you the permission from Electrical inspectorate to run the lift in your building .All statutory fees and other expenses for procuring license should be borne by client.**

79 02 213 213
79 02 215 215
90 72 868 660
AXIMA ELEVATORS (P) LTD.
CTM Complex, Room No: 32 Ambadi Lane, Veliyannur, Thrissur-680021
aximaelevators@gmail.com

Ref:AX/NI/2861/25
19-11-2025

MAINTENANCE

This quotation offers a free maintenance for twelve months. Date of handing over of elevator is subjected to completion of elevator against commissioning. Completion of elevator is basically installation of controller for running of elevator. The date of free maintenance shall be started based on the above mentioned criteria. If there is any delay in building completion, electrical panel installation or permanent power supply, Axima's won't have any responsibility against the timely handing over the elevator. Axima shall not be liable for any loss or damage during this free maintenance period due to any cause beyond our reasonable control including misuse, flood, fire explosion , theft and any other strike or war.

AGREEMENT

a) **Approved Building Plan and Elevation Drawing should be given along with Work Order.**
b) **materials delivery shall be made within 30 days from the date of agreement**
c) **Completion of erection shall be subject to the date of handing over of the Lift-shaft and Machine Room as per our GAD.**
d) **Erection shall be completed within 45 days from the date of handing over the lift shaft.**

Accepted, Signed and Sealed by both Parties

For Axima Elevators (P) LTD | **For and behalf of Purchaser**

Name and Signature | **Name and Signature**

Date: | **Date:**

AXIMA ELEVATORS PVT LTD
CANARA BANK
KOORKANCHERY BRANCH
A/C No -5113201000156
IFSCODE- CNRB0005113
GSTIN: 32AAQCA7974A1ZM
PAN No: AAQCA7974A